

Skunk Creek at I-17			
Painted Staff Gage Rating Table			
	Q (cfs)	Painted Staff (feet)	
	0	0.90	
	50	1.18	
	100	1.24	
	200	1.35	
	300	1.43	
	400	1.51	
	500	1.58	
	800	1.77	
	1,000	1.88	
	1,500	2.13	
	2,000	2.36	
	2,500	2.56	
	3,000	2.76	
	3,500	2.94	
	4,000	3.11	
	4,500	3.28	
	5,000	3.44	
	6,000	3.75	
	7,000	4.04	
	8,000	4.32	
	9,000	4.58	
	10,000	4.84	
	15,000	6.01	
	20,000	7.05	
	25,000	8.01	
	30,000	8.91	
	40,000	10.57	
	50,000	12.09	